


ENSUITES ON SITE LUXURY BATHROOM HIRE

Bathroom Requirements Check List

There are some important factors that you need to consider before hiring one of our bathrooms.

Please read the following requirements carefully.

- **Suitable access is required.** The bathroom requires **2400mm width access** and **2700mm height access**. The higher part of the bathroom is **1800mm wide**. Make sure it will fit where you want it to go. Remember to include the tow vehicle and don't forget roof eaves, pipes, air conditioning systems, trees and shrubs and other obstructions. Don't forget deep driveway gutters. The bathrooms have a sump 200mm off the ground as the picture illustrates to the right. **Bathrooms weigh 700 kilograms**. Email photos of site and access if you are unsure. **Please have all plants trimmed and obstacles removed before delivery.**



- **If we can not install on delivery due to unsuitable access or services you may forfeit your whole hire payment.** A pre-hire inspection can be arranged. **Our representatives are good drivers but are not precision stunt drivers. We will not risk damaging our bathrooms.**

- **Electricity** requires a **10 AMP** power supply of **240 volts**. The bathroom requires **two power points preferably on two separate circuits**. Please ensure the power points are in good condition. **We supply 25 metre leads tagged and tested for your safety.** No power boards or double adaptors can be used. A generator of 5.5 KVA is sufficient for remote locations.



- **Water** needs to be connected so a tap is required. Preferably a garden tap under mains or pump pressure. **We will supply the tap connection and 20 metres of AS2070 drinking quality hose.** Extra hose can be supplied at your request. **Check to see if your tap leaks when turned on.**



- **Sullage** is discharged through a **32mm flexible hose** pumped automatically into your existing sewer via your overflow relief gully, inspection opening, or similar access point (see picture). **Inspect your outside sewer system for a suitable opening.** If in doubt please contact your local plumber or arrange a pre-hire inspection. Septic tanks and enviocycle type systems are fine. We supply all necessary hoses and connections. **Please advise us if the distance to sewer services is greater than 20 metres. Maximum distance is 50 metres with a one metre rise.** We have 1000 litre tanks for hire for sites without sewer or septic facilities. The bathroom can be modified so the shower water is diverted in to your garden. Please advise us in advance if you would like this option.



- Ground must be **reasonably level**. If the site is not level please inform us. The front of the bathroom preferably should be at the highest point.
- If you **supply labour** to manoeuvre the bathroom into place by hand then the **same labour must be provided on pick up or your bond may not be refunded.** The bathroom weighs 700 kilograms.
- A **security deposit** may be required which is refundable once the bathroom and its accessories are returned in the same condition as delivered. A condition report will be completed with you on delivery.
- **Bathrooms must be cleaned out before pick up. Excessive dirt and grime will attract a cleaning fee dependant on time required to return the bathroom to the same condition it was in when handed over to you.**

Please read, sign and return to us the top copy of the Hire Agreement with payment to us to lock in your booking. Unpaid bookings will not be held.

Just like your bathroom at home!